



TENDER 18-25

SEWERMAIN REHABILITATION 2018

ADDENDUM NO. 2

June 19th, 2018

This addendum forms part of the Tender Documents and shall be read, interpreted, and coordinated with all other parts. The costs of all elements contained herein shall be included in the submission. The following revisions, changes, corrections, additions, and or deletions supersede the information contained in the original Documents to the extent referenced and shall become part thereof.

Addendum Item 1 - Questions and Answers

1. Proponent Question:

Are there or will there be cleanouts installed at the property line for main/lateral interface lining?

Response:

The tender specification for the service laterals rehabilitation is to be completed from within the mainline only. An Inspection Chamber or Clean Out is not required when launched from the mainline. Please refer to Supplemental Specification 33 05 27.

2. Proponent Question:

For the MLCIPL work I can only account for 51.4m of MLCIPL work on the drawings 17-525 the 51.4m is for segment 14. However the form of tender shows 81m for segment 14, 10.6m for segment 15 and 23m for segment 16 for a total of 114.6m. Also the instructions to tenderers, Part 1 page 2 of 7 states "Work will also include investigation of approximately 100 service laterals and rehabilitation of approximately 130 lineal meters of service laterals through the use of Cured-In-Place Pipe (MLCIPL) lining method". This gives a 3rd number of 130m. Please clarify.

Response:

The MLCIPL work is specific to Location 9. The tables on Drawings 17-525 Sheet 7 of 7 (Pier Street) indicate approximate lengths of services that require rehabilitation. Segment 14 has 80.3m, Segment 15 has 10.6m, Segment 16 has 23m which = 113.9m (note there is rounding in the schedule of Quantities for item 16.9 at 81 which results in a total of 114.6m.

3. Proponent Question:

As it is indicated on the drawings that some manhole depths are NA which I assume means not available, would it be possible for someone from Public Works to measure the depth of

**CITY OF CAMPBELL RIVER
TENDER 18-25
SEWERMAIN REHABILITATION 2018
ADDENDUM NO. 2**

manholes 2473, 2740, 2535, 2535,2537,2458,2454,2805,2517,2518,2519,998,997,299 and provide this information to us?

Response:

2473=2.0m

2740=2.1m

2535=1.65m

2537=2.4m

2458=2.5m

2454=2.6m

2805=1.3m

2517=3.3m

2518=1.5m

2519=2.0m

998=1.8m

997=1.8m

902=1.5m

299=4.7m (3.0m below grade) with extension to match MoTI Bridge on ramp.

805=2.5m

4. Proponent Question:

Do the laterals had IC's on them? If not is the client planning to install IC's before we do our work?

Response:

Only where noted on Plans. No, as per Plans and Specifications.

End of Addendum

Acknowledgement of this Addendum in your Tender submission is required.

Clinton J. Crook, SCMP, CPSM
Purchasing & Risk Management Officer